

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-173-00014-0000
00014

LEASE NAME Petrie

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 36 TWP. 26 RGE. 1 ~~W~~ (W)

COUNTY Sedgwick

Date Well Completed

Plugging Commenced 4-19-96

Plugging Completed 4-26-96

TYPE OR PRINT
**NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.**

LEASE OPERATOR Pioneer Exploration Company

ADDRESS P.O. Box 691007 Houston, Texas 77269

PHONE#(713) 893-9400 OPERATORS LICENSE NO. 9663

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3392'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD 5-3-96

Formation	Content	From	To	Size	Put In	Pulled out
				9 5/8"	123'	none
				5 1/2"	3389'	144'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each stage. Plugged off bottom with sand to 2638', casing parted, pulled 5-joints of casing. Ran tubing to 2600' pumped 5 sacks 60/40 4% gel cement. Pulled tubing up to 500'. Perforated through tubing and casing at 480', circulated 180 sacks 60/40 4% gel cement to surface. Pulled out of hole. Stayed full. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc. Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1996

Jana Herzberg
Notary Public

My Commission Expires:

