

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-173-20,720-0000

LEASE NAME Petrie

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 36 TWP. 26 RGE. 1 (E) (W)

COUNTY Sedawick

Date Well Completed

Plugging Commenced 4-15-96

Plugging Completed 4-18-96

LEASE OPERATOR Pioneer Exploration Company

ADDRESS P.O. Box 691007 Houston, TX 77269

PHONE (713) 893-9400 OPERATORS LICENSE NO. 9663

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

5-3-96

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	211'	none
				5-1/2"	3570'	2363'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each sack. Plugged off bottom with sand to 3340', dumped 5 sacks cement. Shot casing at 2350'. Pumped 8 sacks gel at 2350', pulled casing up to 250' pumped 110 sacks cement (60/40 POZMIX 4% gel) pulled 2 joints casing, pumped 65 sacks Class A cement down 5-1/2" casing to surface - Pulled rest of casing. Surface pipe full. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc. - Chase, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524.

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 96

James W. [Signature]
Notary Public

My Commission Expires:

