

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division,
State Corporation Commission,
500 Bittling Building,
Wichita, Kansas.

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

RECEIVED
JAN 22 1936
BY 22-36 [Signature]

X		

NORTH Sedgewick County. Sec. 12 Twp. 26s Rge. 1 (E) East(w) WELL NO. 8

Lease Name A. C. Wright
 Lease Owner Continental Oil Company
 Office Address Ponca City, Oklahoma.
 Character of Well (Oil, Gas or Dry) DRY Total Depth of Well 3375 Feet
 Date, well, completed September 3, 1929
 Application for plugging and log of well filed 7-8-35 & 1-6- 1936 193
 Application for plugging approved 7-29-35 & 1-7- 1936 193
 Plugging Commenced October 5 1935
 Plugging Completed January 11, 1936
 Reason for abandonment of well ~~or producing formation~~ Dry

If a producing well is abandoned, date of last production July 31 1935
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Officer who supervised plugging of this well Mr. H. C. Smith
 Producing formation Dolomite Depth to top 3370' Bottom 3375'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				20"	52'	none
				8-5/8"	3030'	2048'
				7"OD.	3552'	2672'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ten sacks cement dumped at 3375' - Ripped 7"OD. casing off at 2675 and pulled same - Ripped 8 5/8"OD. casing off at 2652' and raised to 2555' bridged hole at 2652 and filled with rock to 2645' and dumped 15 sacks at 2645', which filled hole to 2602' and dumped 6 sacks cement at 2602', which filled hole to 2574' - Filled hole with rock from 2574' to 2565' and dumped 2 sacks cement at 2565' - Cemented 8 5/8"OD. casing with 125 sacks cement, Halliburton method. Drilled out cement to 2590' - Tested out and found to be non-commercial.
 Filled hole with mud to 2540' and ripped 8 5/8"OD. casing off at 1900' and pulled same, filled hole with mud to 100' and ran 17" dry hole wood plug to 85' and filled with mud to 80' and dumped 10 sacks cement at 80' and filled hole with mud to within five feet of cellar and capped with 10 sacks cement.

PLUGGING
 FILE NO. 12-2621E
 BOOK PAGE 31 - LINE 16
 11-23 P.B.

All mud dumped in hole
 Cement put in hole with cement dump bailer

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes
 Was exception made? _____ If so describe _____

Correspondence regarding this well should be addressed to Mr. L. P. Carpenter
 Address % Continental Oil Company, Ponca City, Oklahoma.

STATE OF Kansas COUNTY OF Sedgewick, ss.

J. P. Neel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. P. Neel
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18 day of January, 1936.

My commission expires 1/23/39
O. R. Schappell Notary Public.