

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Bittling Building,
Wichita, Kansas.

RECEIVED
NOV 21 1935
7-21-35
Ha

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

			X

Locate well correctly on above
640 A. Plat

Sedgwick County. Sec. 12 Twp. 26s Rge. (E) 1 (W) 1
 Lease Name A. C. Wright Lease Well No. 10
 Lease Owner Continental Oil Company
 Office Address Ponca City, Oklahoma.
 Character of Well (Oil, Gas or Dry) DRY Total Depth of Well 3369 Feet
 Date, well, completed December 12, 1929
 Application for plugging and log of well filed June 11. & September 30 1935
 Application for plugging approved June 12 & September 30 1935
 Plugging Commenced July 4, 1935
 Plugging Completed October 27, 1935
 Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production January 1, 1933
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? Yes

Name of Conservation Officer who supervised plugging of this well H. C. Smith
 Producing formation Dolomite Depth to top 3366 Bottom 3369
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				20"	60'	None
				15 1/2"	225	225
				12 1/2"	1330	1330
				10"	2055	2055
				8 1/2"	3030	2269
				6 5/8"	3350	2557' 9"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

10 Sacks cement was dumped at 3369' - Ripped 7"OD. casing off at 2770' and pulled same out - Ripped 8 5/8"OD. casing off at 2600' and raised to 2550'. Set bridge at 2610' and dumped 7' of stone and 10 sacks of cement and filled with stone to 2567' and dumped two sacks of cement at 2567'. Cemented 8 5/8"OD. casing at 2555' with 125 sacks cement - Halliburton method. drilled out cement from 2551 to 2582' and acidized with 2000 gal acid and tested well and found to be dry, drilled out cement from 2582' to 2595' and drove 150# lead wool at 2595' and dumped 10 sacks of cement - Tested well and found to be dry -

Filled hole with mud from 2595 to 2200' and ripped 8 5/8"OD. casing off at 2200' and pulled same, filled hole with mud from 2200' to 60' and drove 15 1/2" dry hole wood plug to 62' and dumped 8 sacks cement on top of plug and filled with mud to top of 20" casing and capped with 7 sacks cement.

PLUGGING
 FILE SEC 12 TWP 26 R 1 W
 BOOK PAGE 20 LINE 37

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations? Yes
 Was exception made? _____ If so describe _____

Correspondence regarding this well should be addressed to Mr. L. P. Carpenter
 Address % Continental Oil Compan, Ponca City, Okla.

STATE OF Kansas COUNTY OF Sedgwick, ss.

H. M. Walden (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. M. Walden
Valley Center, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 19 day of November, 1935

My commission expires 1/23/39
O. R. Chappel Notary Public.