

B
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address Box 1098, Liberal, Kansas

Lease Name George S. Frey Well No. 1-0

Location SE NW Sec. 19 Twp. 27 Rge. 33 (E) (W)

County Haskell Total Depth 2773'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated None

Plugging Contractor J.D. Well Service

Address Liberal, Kansas License No. 632

Operation Completed: Hour 6:00PM Day 11 Month 4 Year 1970

The above well was plugged as follows:

10 3/4" to 600' circulated w/ cement. 7" to 2624' cemented.

5 1/2" liner 2590' to T.D. No Perforations

Plug bottom w/ 150 sacks cement. Top of cement 2350'

Mud 2350' to 600' Spotted 30 sacks cement 600' to 480'

Mud 480' to 40' Plug, Halls & 10 sacks cement 40' to 0'.

Halliburton Pump Truck. No Pipe Pulled

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edgar J. Egan*
Well Plugging Supervisor

DATE 4/15/70

INV. NO. 1721-u