

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Helmerich & Payne Inc.

Complete Address: Box 558, Garden City, Kansas

Lease Name Winger Well No. 1

Location C SW SW Sec. 26 Twp. 27 Rge. 31 (~~EA~~) (W)

County Haskell Total Depth 5421'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Rine Drilling Co.

Address: 300 W. Douglas, Wichita, Kansas License No.

Operation Completed: Hour 5:30PM Day 5 Month 3 Year 1968

The Above well was plugged as follows:

8 5/8" to 881' circulated w/cement. Mud 5421' to 880'

Spotted 35 sacks cement 880' to 780' Mud 780' to 45'

Plug, Hulls & 15 sacks cement 45' to 0' Halibuton Pump Truck.

Left Approx. 880' of 4 1/2" drillpipe in hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edward E. ...*
Well Plugging Supervisor

DATE 3/14/68
INV. NO. 7416-u