

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-070789

9-25

API Number: 155
15-055-21117-0000

C SW SW SECTION 33 TWP 25 RANGE 08W

OPERATOR LICENSE #3536 660 FEET FROM S SECTION LINE
OPERATOR RAMCO ENERGY CORP. 4290 FEET FROM E SECTION LINE
NAME & P.O. BOX 340
ADDRESS GREAT BEND, KS 67530

LEASE NAME MELVIN MINOR #4
COUNTY RENO
WELL TOTAL DEPTH 3970' 129.03
PIPE 5 1/2" @ 3969'
SURFACE CASING 8 5/8" @ 347

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING AND SALVAGE

ADDRESS: P.O. BOX 467, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 25 MONTH: 9 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKES' TESTING AND SALVAGE PHONE: (319) 938-2943

WERE: SAND TO 3775' AND 5 SACKS
35 SACKS @ 1200'
35 SACKS @ 700'
35 SACKS @ 400'
200' TO 0

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 4:30 DAY: 25 MONTH: 9 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3775' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 3000'. PULLED TO 1200', PUMPED 35 SACKS. PULLED TO 700', PUMPED 35 SACKS. PULLED TO 400', PUMPED 35 SACKS. PULLED TO 200', CIRCULATED CEMENT TO SURFACE

RECEIVED
KANSAS CORPORATION COMMISSION
10-7-98
OCT 07 1998

REMARKS: ALLIED #2522, 60/40 POZ, 4% GEL.

I DID OBSERVE THIS PLUGGING.

JACK LUTHI

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 10-7-98
INV. NO. 51432

FORM CP-2/3
REV. 3/90