

2-070590

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

1-11

API NUMBER: 15-155-21,191-0000

S a S w SW SECTION 9 TOWNSHIP 25 RANGE 9W
330 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR LICENSE #3911
OPERATOR RAMA Operating Co., Inc.
NAME & PO Box 159
ADDRESS Stafford, KS 67578

LEASE NAME: Wilden #1-9
COUNTY: Reno
WELL TOTAL DEPTH: 4030'
CONDUCTOR PIPE: 5 1/2" @ 4029'
SURFACE CASING: 8 5/8" @ 225'

130.98

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Mike's Testing & Salvage
ADDRESS: Chase, KS LICENSE: #

COMPANY TO PLUG AT: HOUR: 10:30 DAY: 11 MONTH: 1 YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM: Manny

COMPANY NAME: Same PHONE:

WERE: Sand to 3800' and 5 sacks of common 35 sacks at 1400'
35 sacks at 850' 270' to 0'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { X } NONE { }

COMPLETED: HOUR: 3:00 DAY: 11 MONTH: 1 YEAR: 1996

ACTUAL PLUGGING REPORT: Sanded bottom to 3800' and 5 sacks of common shot 5 1/2" casing off at 2721'. Pulled to 1400' Pumped 35 sacks Pulled to 850' Pumped 35 sacks Pulled to 270' Circulated cement to surface.

REMARKS: Allied #1867 60/40 4%

I DID OBSERVE THIS PLUGGING.

RECEIVED
KANSAS CORPORATION COMMISSION

2-26-96
FEB 26 1996

Jack Luthi (AGENT)

CONSERVATION DIVISION
WICHITA, KS
FORM CP-2/3
REV. 3/90

INVOICED

DATE 2-27-96

INV. NO. 44884

DW