

1-19

2-070547

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-155-21,247-00-00  
C W/2 NW NE, SECTION 13 TOWNSHIP 25 RANGE 9 W

OPERATOR LICENSE # 5058 4620 FEET FROM S SECTION LINE  
2310 FEET FROM E SECTION LINE

OPERATOR GRIGGS OIL INC  
NAME & 100 N MAIN, SUITE 1010  
ADDRESS WICHITA, KS 67202

LEASE NAME: BROOKS-JOHNSON 1-13 130,00  
COUNTY: RENO  
WELL TOTAL DEPTH: 4000' PB 3918'

PIPE: 5 1/2" @ 3969'

SURFACE CASING: 8 5/8" @ 182'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_  
PLUGGING CONTRACTOR: MIKES TESTING AND SALVAGE  
ADDRESS: \_\_\_\_\_ LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 19 MONTH: 1 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: WEESE DUNCE  
COMPANY NAME: SAME PHONE: 316-  
WERE: SAND TO 3800 AND 5 SACKS  
35 SACKS TO 1500  
35 SACKS TO 800  
250' TO 0

PLUGGING PROPOSAL RECEIVED BY: J LUTHI  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL {  } PART {  } NONE {  }

COMPLETED: HOUR: 12:30 DAY: 19 MONTH: 1 YEAR: 1995  
ACTUAL PLUGGING REPORT:

SANDED BOTTOM TO 3800' AND 5 SACKS OF COMMON SHOT 5 1/2" CASING OFF  
AT 3000' PULLED TO 1500' PUMPED 35 SACKS PULLED TO 800' PUMPED 35  
SACKS PULLED TO 250' CIR CEMENT TO SURFACE

REMARKS: ALLIED #1171, 60/40 4% GEL  
I DID OBSERVE THIS PLUGGING.

Jack Luthi  
Jack Luthi (AGENT)

FORM CP-2/3

REV. 3/90

RECEIVED  
KANSAS CORPORATION COMMISSION

INVOICED

DATE 2-15-95  
INV. NO. 42194

FEB 14 1995  
2-14-95  
CONSERVATION DIVISION  
WICHITA, KS