

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

9-6

API NUMBER: 15-155-21322-0000

C W/2, SW, SECTION 13 TOWNSHIP 25 RANGE 09W

OPERATOR LICENSE # 3911

1320 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR RAMA OIL COMPANY, INC.
NAME & BOX 159
ADDRESS STAFFORD, KS 67578

LEASE NAME: MOORE #1-13 ^{130.00}

COUNTY: RN Reno

WELL TOTAL DEPTH: 4000'

PIPE: 5 1/2" @ 3982'

SURFACE CASING: _____

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKES TESTING

ADDRESS: P.O. BOX 209, CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 06 MONTH: 9 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: SAME PHONE: 316-

WERE: SAND TO 3764' 5 SKS.
35 SKS. 1300', 35 SKS. 800', 270' TO 0'.

PLUGGING PROPOSAL RECEIVED BY: J.L.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { _____ } NONE { _____ }

COMPLETED: HOUR: 2:00 DAY: 06 MONTH: 9 YEAR: 1995

ACTUAL PLUGGING REPORT:
SANDED BOTTOM TO 3764' & 5 SKS. OF COMMON. SHOT 5/12"
CASING OFF @ 2502' PULLED TO 1300' PUMPED 35 SKS.
PULLED TO 800' PUMPED 35 SKS. PULLED TO 270' CIR. CMT.
TO SURFACE.

REMARKS: ALLIED #1389 60/40 POZ. 4% GEL.

I DID OBSERVE THIS PLUGGING.

Jack Luth
RECEIVED
Jack Luth
KANSAS CORPORATION COMMISSION
9-8-95
SEP 08 1995

FORM CP-2/3
REV. 3/90

INVOICED

DATE 9-26-95

INV. NO. 43596

CONSERVATION DIVISION
WICHITA, KS