

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

8-6

API NUMBER: 15-155-21,180-0000

C NE NE, SECTION 20 TOWNSHIP 25 RANGE 9W

OPERATOR LICENSE # 31160 4620 FEET FROM S SECTION LINE
OPERATOR PHILLIPS EXPLORATION CO. 660 FEET FROM E SECTION LINE
NAME & ADDRESS 2338 BROMFIELD CIRCLE WICHITA, KS 67226

LEASE NAME: JOY ROYSE #1
COUNTY: RENO
WELL TOTAL DEPTH: 4040' 131.30
PIPE: 5 1/2" @ 4035'
SURFACE CASING: 8 5/8" @ 170'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: D S & W WELL SERVICE
ADDRESS: P.O. BOX 231, CLAFLIN, KS 67625 LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 6 MONTH: 8 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: KEN STRUB

COMPANY NAME: PHILLIPS PETROLEUM CO. PHONE:

WERE: SAND TO 3800' AND 5 SACKS
35 SACKS @ 1400'
35 SACKS @ 800'
250' TO 0

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 16 1996

PLUGGING PROPOSAL RECEIVED BY: J.L.

8-16-96
CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 2:00 DAY: 6 MONTH: 8 YEAR: 1996

ACTUAL PLUGGING REPORT: SHOT 5 1/2" CASING OFF AT 3025'. SANDED BOTTOM TO 3800' AND 5 SACKS OF COMMON. PULLED TO 1400'. PUMPED 35 SACKS. PULLED TO 800'. PUMPED 35 SACKS. PULLED TO 250'. CIRCULATE CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #7242

INVOICED

DATE 8-19-96
INV. NO. 46290

I DID OBSERVE THIS PLUGGING.

JACK LUTHI
FORM CP-2/3
REV. 7/96

DW