

To: 1020491 8-21
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-17,513
SW SW SW SW, SEC. 27, T. 28 S, R 39 W/E
150 feet from S section line
175 feet from W section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5952
Operator: Amoco Production Company
Name: Amoco
Address: P.O. Box 800, Rm. 2444
Denver, CO 80201

Lease Name Scrogum Well # 1-A
County Stanton 50.63
Well Total Depth 1558 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 706

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pullers License Number 6497
Address Box E, Sublette, KS 67877

Company to plug at: Hour: 1 p.m. Day: 21 Month: 8 Year: 19 92

Plugging proposal received from Ed Eves
(company name) Midwest Casing Pullers (phone) 316-675-8349

Work: 5 1/2" at 1523' w/500 sx cement, PBTD 1523', Perfs at 1354-1495',
Fiberglass

1st plug set CIBP at 1340' with 2 sx cement on top,

2nd plug pump down 5 1/2" and fill to surface.

Check backside.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 21 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 1340' with 2 sx cement on top with bailer,

2nd plug pumped down 5 1/2" and filled to surface, pressure to 800#, used 100 sx Class H cement.
8 5/8" & 5 1/2" cemented to surface.

Checked backside of 5 1/2".

RECEIVED
STATE CORPORATION COMMISSION

8-25-92 AUG 25 1992

Remarks: Used Class H cement by Midwest Casing Pullers. No casing recovery
Conservation Division, Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 8-27-92

Signed Glenn R Barlow
(TECHNICIAN)

WV. NO. 36062