

R 100155

8-28

15-187-00328-0000

1

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Spud date 12/17/52

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name: P.O. Box 351
Address: Liberal, KS 67905-0351

NE NE SW, SEC. 10, T 28 S, R 40 W/E
2540 feet from S section line
2540 feet from E section line
Lease Name Plummer Well # 1-10
County Stanton 98.03
Well Total Depth 2401 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 300

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 27 Month: 8 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 7" at 2194' w/150 sx cement, Open hole 2194-2401'

1st plug pump 40 sx cement over open hole,

2nd plug at 1650' with 50 sx cement,

3rd plug at 650' with 80 sx cement,

4th plug at 330' with 70 sx cement, 5th plug at 40' with 20 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12 p.m. Day: 28 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 90 bbls. mud down 7". Pulled tubing to 2000' and pumped 40 sx cement with 300 lbs. hulls. from 2194-1994',

2nd plug circulated hole with mud and spotted 50 sx cement from 930-830',

3rd plug pulled to 400' and spotted 75 sx cement from 400-250',

4th plug pulled to 40' and spotted 20 sx cement from 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

9-29-97

Remarks: Used common cement by Sargent & Horton. Recovered 930' of 7" casing.
(If additional description is necessary, use BACK of this form.)

I (XXX / did not) observe this plugging.
DATE 9-11-97

INV. NO. 48957

Signed Gary Winters (TECHNICIAN)

8-28 OCT 30 1997