

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20979-00-01  
Spot: W2NENESW Sec/Twnshp/Rge: 28-28S-40W  
2310 feet from S Section Line, 2100 feet from W Section Line  
Lease/Unit Name: GARY FLOYD Well Number: 1-1128  
County: STANTON Total Vertical Depth: 5620 feet

Operator License No.: 32309  
Op Name: PRESCO WESTERN LLC  
Address: 1775 SHERMAN STE 2950  
DENVER, CO 80203

Conductor Pipe: Size feet: 8 1/2 - 65  
Surface Casing: Size 8.625 feet: 1831 WITH 750 SX CMT  
Production: Size 4.5 feet: 5612 WITH 250 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/24/2003 10:00 AM

Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.

Proposal Rcvd. from: RODNEY GONZALES Company: PRESCO WESTERN Phone: (303) 864-1881

Proposed Plugging Method: CIBP @ 4980'. SPOT A 20 SX CMT PLUG ABOVE 4 1/2" CASING STUB. 50 SX CMT AT 1850'. 25 SX CMT AT 750'. 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/24/2003 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5529'. PERFS AT 5034-39 & 5372-81'. PORT COLLAR AT 3050' NEVER CEMENTED. SET CIBP @ 4980' WITH 2 SX CMT ON TOP WITH BAILER. LOAD HOLE WITH MUD. 1ST PLUG AT 4070' WITH 20 SX CMT. DISPLACE WITH 55 BBL MUD. 2ND PLUG PULL OUT OF HOLE TO 1850'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH 30 BBL MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 650' & PUMP 25 SX CMT. DISPLACE WITH MUD. 4TH PLUG PULL OUT OF HOLE TO 40' & PUMP 15 SX CMT TO SURFACE.

RECEIVED


FEB 03 2003

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4100' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PARTIAL  
(TECHNICIAN)

INVOICED

DATE 2-4-03

WV. NO. 2003061150

F001 CP 1/3