

1 031362

5-081-5002-0000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

10-4

API NUMBER 15- Drill completion 11/28/64

C SW NE, SEC. 8, T 28 S, R 34 W/R

3300 feet from S section line

1980 feet from E section line

Lease Name Fletcher Well # 21C

County Haskell 178.75

Well Total Depth 5500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1926

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: OXY USA INC.

Address P.O. Box 26100

Oklahoma City, OK 73126-0100

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor J.W. Gibson Well Service License Number 5866

Address 518 17th St., Ste. 1250, Denver, CO 80202

Company to plug at: Hour: 8 a.m. Day: 2 Months: 10 Year: 19 95

Plugging proposal received from Mike Fink

(company name) OXY USA INC. (phone) 1-800-569-3613

work: 5 1/2" at 5461' w/400 sx cement, PBSD 5430', Perfs at 5240-5362'

1st plug set GIBP at 5190' with 1 sx cement on top.

2nd plug fill 5 1/2" X 8 5/8" annulus with cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1995

Plugging Proposal Received by Steve Durrant

CONSERVATION DIVISION
Wichita, Kansas
Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7 p.m. Day: 4 Month: 10 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set GIBP at 5190' with 1 sx cement on top. Filled casing

with mud. 10/2/95 Tried to bull head cement between 5 1/2" & 8 5/8". After pumping 47 sx,

cement circulated out hole in surface pipe. Shut down. Displaced pipe with mud.

Filled 5 1/2" from 850-0'. Pumped 30 sx cement at 3010', Pumped 30 sx cement at 1925'.

Pumped 86 sx cement at 850' and lost circulation up 5 1/2". Shut down. 10/3/95 Tripped in with

tubing and tagged TOC at 625'. Shut down. 10/4/95 Perforated at 610', filled 5 1/2" casing

to surface with 140 sx.

Remarks: Used common cement by Gibson Well Serv. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-27-95

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 43878

10-4