

100004

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-081-20,698-0002

C SW SW, SEC. 27, T 28 S, R 34 W/E
660 feet from S section line
4620 feet from E section line

12-13

TECHNICIAN'S PLUGGING REPORT
Operator License 5003

Lease Name Doerksen A Well 4-27
County Haskell

Operator: McCoy Petroleum Corporation
Name
Address 3017 N. Cypress
Wichita, KS 67226-4003

Well Total Depth 5660 183.95 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1883

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor J.W. Gibson Well Service License Number 5866

Address P.O. Box 466, Ulysses, KS 67880

Company to plug at: Hour: 3:30 p.m. Day: 13 Month: 12 Year: 19 95

Plugging proposal received from Tim Hintergardt

(company name) J.W. Gibson Well Service (phone) 316-353-1002

logs: 5 1/2" at 5656' w/ 450 sx cement, PBD 5610'; Perfs at 4168-70, 5420-32, 5400-12, 5300-10'
CIBP at 4250'

1st plug set CIBP at 4120' with 2 1/2 sx cement on top, load hole with mud,

2nd plug set 40 sx cement plug at stub, 3rd plug set 40 sx cement plug at 650',

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5 p.m. Day: 13 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4120' with 2 sx cement on top,

2nd plug set 40 sx cement plug at shot point of 1388',

3rd plug pull out of hole to 650' and set 40 sx cement plug,

4th plug pull out of hole to 40' and set 10 sx cement plug.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 21 1995

12-21-95
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used common cement by J.W. Gibson. Recovered 1388' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I will (and may) observe this plugging.

DATE JAN 09 1996
INV. NO. 44446

Signed Gary Winters (TECHNICIAN)