

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-10213-00-00  
Spot: NWSE Sec/Twnshp/Rge: 32-28S-34W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: MCCOY FRANK Well Number: 3-32  
County: HASKELL Total Vertical Depth: 5531 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 4750 WITH 375 SX CMT  
Surface Casing Size: 8.625 feet: 1860 WITH 750 SX CMT  
*8/ 17976*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/16/2003 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 4630' WITH 2 SX CMT. PLUG AT 1860' WITH 50 SX CMT. PLUG AT 750' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/17/2003 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:  
PBTD 5451'. PERFS AT 4689-4702'. DV TOOL @ 3060'. SET CIBP @ 4630' WITH 2 SX CMT ON TOP. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE TO 1860'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 750'. SDON. LOAD HOLE WITH MUD & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED  
OCT 14 2003  
KCC WICHITA

Remarks: USED COMMON CMT BY SARGENTS. RECOVERED 1902' OF 5 1/2" CASING.  
Plugged through: CSG

District: 01

RECEIVED  
SEP 30 2003  
KCC Dodge City

Signed Jim Holland (TECHNICIAN)

INVOICED  
DATE 10-14-03  
INV. NO. 2004060607

Fdmr CP 2/3  
*[Signature]*