

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-10212-00-00
Spot: SESE Sec/Twnshp/Rge: 32-28S-34W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: MCCOY UNIT Well Number: 2-32
County: HASKELL Total Vertical Depth: 5503 feet

Operator License No.: 4549 Production Casing Size: 5.5 feet: 5491 WITH 300 SX CMT
Op Name: ANADARKO PETROLEUM CORPORATI Surface Casing Size: 8.625 feet: 1846 WITH 750 SX CMT
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380 # 17885

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/10/2003 2:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2925' WITH 2 SX CMT. PLUG AT 1870' WITH 50 SX CMT. PLUG AT 700' WITH 30 SX CMT. PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/10/2003 6:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5451'. PERFS AT 4689-4702 & 5417-43'. DV TOOL @ 2978'. TUBING & PACKER STUCK IN HOLE. SET CIBP @ 2927' WITH 2 SX CMT. LOAD HOLE WITH MUD & PRESSURE TO 500#. 1ST PLUG PULL OUT OF HOLE TO 1220'. CIRCULATE HOLE & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 700'. LOAD HOLE & PUMP 30 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT TO SURFACE.

RECEIVED
OCT 01 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1227' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
SEP 15 2003
KCC Dodge City

Signed Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 10-1-03
INV. NO. 2004060.558

Form CP 2/03