

To: 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-15-87  
API NUMBER 15-081-75-003 66170-0000  
SE NW, SEC. 34, T. 28 S., R. 34 W/E  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952  
Operator: Amoco Production Company  
Name & Address P.O. Box 432  
Liberal, KS 67901

Lease Name K.H. Reimer "B" Well # 1  
County Haskell 182.10  
Well Total Depth 5603 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 752

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497  
Address Box E, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 15 Month: 6 Year: 1987

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 5594' PBTD 5551' Perfs at 5293-98, 5438-42'

- 1st plug set CIBP at 5200' and dump 2 sx cement on top of plug,
- 2nd plug at 1440' with 50 sx cement,
- 3rd plug at 800' with 50 sx cement,
- 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 15 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5200' with 2 sx cement on top,

- 2nd plug at 1440' with 50 sx cement,
- 3rd plug at 800' with 50 sx cement,
- 4th plug at 40' with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 19 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 1440' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If desired, recipient) observe this plugging.

INVOICED  
DATE 6-22-87  
INV. NO. 17274 6-15

Signed Richard W. Lacey  
(TECHNICIAN)