

1 110154

9-10

R 16

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-081-20,549-0000  
C W/2 SE, SEC. 18, T 28 S, R 32 W/E

1285 feet from S section line  
1945 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4328

Lease Name Bear Well # 2-18

Operator: Global Natural Resources

County Haskell 183.17

Name & Address P.O. Box 4682

Well Total Depth 5636 feet

Houston, TX 77210

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1861

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor BEREDCO, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 10:15 a.m. Day: 10 Month: 9 Year: 19 89

Plugging proposal received from Kent Johnson

(company name) BEREDCO Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1810'

1st plug at Base Council Grove with 50 sx cement,

2nd plug at Base Chase with 50 sx cement, 3rd plug at 1890' with 40 sx cement,

4th plug at 600' with 40 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole Plugging Proposal Received by James R. Kapp  
with 10 sx cement. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:15 p.m. Day: 10 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3500' with 50 sx cement,

2nd plug at 2550' with 50 sx cement,

3rd plug at 1890' with 40 sx cement,

4th plug at 600' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement. Used 60/40 Pozmix 6% gel by Halliburton.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-18-89

INV. NO. 25897

9-10

Signed James R. Kapp (TECHNICIAN)

RWL

STATE CORPORATION COMMISSION  
RECEIVED  
SEP 12 1989  
CONSERVATION DIVISION  
Wichita, Kansas

9-12-89

