

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20963-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 2-28S-33W
1500 feet from N Section Line, 2500 feet from E Section Line
Lease/Unit Name: ANSCHUTZ A UT Well Number: 3
County: HASKELL Total Vertical Depth: 3023 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: PO BOX 4358
HOUSTON, TX 77210

Conductor Pipe: Size feet: 8 98.25
Surface Casing: Size 8.625 feet: 887 WITH 450 SX CMT
Production: Size 5.5 feet: 3013 WITH 425 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/07/2001 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT TO PLUG BOTTOM. 1ST PLUG AT 1500' WITH 25 SX CMT. 2ND PLUG AT 900-0'. CIRCULATING CMT TO SURFACE. CHECK ANNULUS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/02/2001 4:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PERFS AT 2730-40, 2760-70, 2796-2806'. PBD 2785'. CMT RETAINER AT 2785' OVER BOTTOM PERFS AT 2796-2806'. 1ST PLUG PUMP 300# HULLS AND 25 SX CMT FOR BOTTOM PLUG. 2ND PLUG PUMP 26 BBL MUD SPACER TO 1500'. PUMP 25 SX CMT. 3RD PLUG PUMP 9 BBL MUD SPACER TO 900'. CHECK FLUID LEVEL WITH WIRELINE. PUMP 100 SX CMT FROM 900' TO SURFACE. PRESSURED TO 350# AND SHUT IN. HOOK ON TO BACKSIDE AND PUMP 15 SX CMT. PRESSURED TO 500# AND SHUT IN.

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Jim Holland PIRTH
(TECHNICIAN)

RECEIVED

DEC 31 2001 INVOICED DEC 27 2001

WICHITA DATE 01-02-02

WV. NO. 2002061115

Form 01-21