

1-120390

3-31

224 R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-081-20,612-6000  
C NE SW, SEC. 8, T 28 S, R 34 W/E  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3931  
Operator: Panada Exploration  
Name & Address 6846 S. Canton, Suite 500  
Tulsa, OK 74136

Lease Name Dubois Estate Well # 1-8  
County Haskell  
Well Total Depth 5767 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1800

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling, Inc. License Number 5107  
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 31 Month: 3 Year: 19 90

Plugging proposal received from John Schlenz  
(company name) H-30 Drilling, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1800'  
1st plug at 2920' with 100 sx cement, 2nd plug at 1830' with 50 sx cement,  
3rd plug at 920' with 60 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 7 a.m. Day: 31 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2920' with 100 sx cement,  
2nd plug at 1830' with 50 sx cement,  
3rd plug at 920' with 60 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-12-90 APR 05 1990 4-05 90

Signed Duane Rankin (TECHNICIAN)

INV. NO. 27831 3-31 MAY 24 1990

FORM MUST BE TYPED  
EFFECTIVE DATE: 3/11/90

State of Kansas 081-20,612-0000  
NOTICE OF INTENTION TO DRILL  
Must be approved by the K.C.C. five (5) days prior to commencing well

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Expected Spud Date ... March ... 15 ... 1990 ...  
month day year

..C.. .NE. .SW. Sec .8.. Twp .28.. S, Rg .34. X East  
1980  
3300 feet from South line of Section  
feet from East line of Section  
(Note: Locate well on Section Plat Below)

OPERATOR: License # 03931  
Name: Panada Exploration  
Address: 6846 S Canton, Suite 500  
City/State/Zip: Tulsa, Ok 74136  
Contact Person: Mark Repasky  
Phone: (918)492-5806

County: Haskell  
Lease Name: Dubois Estate Well #: 1-8  
Field Name: North Eubank

CONTRACTOR: License #: 5107  
Name: H-30 Drilling, Inc.

Is this a Prorated Field?  yes  no  
Target Formation(s): Morrow  
Nearest lease or unit boundary: 560 feet  
Ground Surface Elevation: 300 feet MSL  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no  
Depth to bottom of fresh water: 376 feet 540'  
Depth to bottom of usable water: 750 feet 950'  
Surface Pipe by Alternate:  1  2  
Length of Surface Pipe Planned to be set: 1800 feet  
Length of Conductor pipe required: None  
Projected Total Depth: 5800 feet  
Formation at Total Depth: St. Louis  
Water Source for Drilling Operations: unknown  
... well ... farm pond ... other

Well Drilled For: Well Class: Type Equipment:  
..X Oil ... Inj ... Infield ... Mud Rotary  
... Gas ... Storage X. Pool Ext. ... Air Rotary  
... OAWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? .... yes X.. no  
If yes, total depth location: \_\_\_\_\_

Exp. 9/6/90

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken? .... yes X.. no  
If yes, proposed zone: \_\_\_\_\_

AFFIDAVIT

970' Alt. I Req.

PUSHER John Schlemm  
TD 5767 FORMATION St. Louis  
SURFACE PIPE 8 3/8" @ 1800'  
ANHYDRITE 1600' ELEVATION  
STARTING TIME & DATE 4:00 AM 3-31-90  
COMPLETION TIME & DATE 7:00 AM 3-31-90  
1st PLUG @ 2920 FT. WI 100 SX  
2nd PLUG @ 1830 FT. WI 50 SX  
3rd PLUG @ 920 FT. WI 40 SX  
4th PLUG @ 40 FT. WI 10 SX  
RAT HOLE CIRCULATED WI 15 SX  
MOUSE HOLE CIRCULATED WI 10 SX  
WATER WELL PLUGGED WI \_\_\_\_\_ SX  
CEMENT COMPANY Howco  
TECHNICIAN D.R.  
TYPE OF CEMENT 60-46-670  
3-20-90  
8 5/8 @ 1800'

Grid with depth markers: 5280, 4950, 4620, 4290, 3960, 3630, 3300, 2970, 2640, 2310, 1980, 1650, 1320, 990, 660, 330

RECEIVED  
APR 05 1990  
CONSERVATION DIVISION  
Wichita, Kansas

Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.