

To: 1 090250
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-187-20,658-0000 140 R
App. N/2 SE SE, SEC. 32, T. 28 S, R. 40 W/EX

TECHNICIAN'S PLUGGING REPORT

810 feet from S section line
660 feet from E section line

Operator License # 30606
Operator: Murfin Drilling Company, Inc.
Name & Address 250 N. Water, Ste. 300
Wichita, KS 67202

Lease Name Rorick Well # 1
County Stanton
Well Total Depth 5800 188.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1672

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company, Inc. License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 27 Month: 1 Year: 19 93

Plugging proposal received from Tom Heskett
(company name) Murfin Drilling Company (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1720'
1st plug at 2520' with 100 sx cement, 2nd plug at 1720' with 80 sx cement,
3rd plug at 600' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 2 a.m. Day: 28 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2520' with 100 sx cement,
2nd plug at 1720' with 80 sx cement,
3rd plug at 600' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
Additional description is None (BACK of this form.)
I ~~did~~ did not observe this plugging.
DATE: 2-18-93
INV. NO. 37284
1-28

RECEIVED
STATE CORPORATION COMMISSION
FEB - 3 1993
CONSERVATION DIVISION
WICHITA, KANSAS
(TECHNICIAN)

FORM CP-2/3

EFFECTIVE DATE: 1-11-93

State of Kansas

187-20,658

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

APPROX

Expected Spud Date 01 12 93 155 N/2 SE SE Sec 32 Twp 28 S. Rg 40 X West

OPERATOR: License # 30606 Murfin Drilling Company, Inc. Address: 250 N. Water, Suite 300 City/State/Zip: Wichita, KS 67202 Contact Person: Jack E. Goss Phone: 316/267-3241

810 feet from South / North line of Section 660 feet from East / West line of Section IS SECTION X REGULAR (REGULAR?)

(NOTE: Locate well on the Section Plat on Reverse Side County: Stanton

Lease Name: Rorick Well # 1

Field Name:

Is this a Pretest/Spaced Field? yes X no

Target Formation(s): Morrow, Miss. St., Lonia

Nearest lease or unit boundary: 660'

Ground Surface Elevation: 3291 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 200 450'

Depth to bottom of usable water: 500 600'

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 1650'

Length of Conductor pipe required: D/A

Projected Total Depth: 5850'

Formation at Total Depth: Miss St. Louis

Water Source for Drilling Operations: well farm pond X other

DNR Permit #: applied for

Will Cases be Taken?: yes X no

If yes, proposed zone:

CONTRACTOR: License # 30606 Murfin Drilling Company, Inc.

Well Drilled For: Well Class: Type Equipment: X Oil Infield X Mud Rotary Gas Storage Pool Ext. Air Rotary GSDO Disposal X Wildcat Cable Seismic: # of Holes Other

If GSDO: old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional: Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location:

620' Alt. I Req.

AFFIDAVIT

Exg. 7/6/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will

Pusher Tom Horkett Called Bawles on 5/10/92 SPUD DATE 1-15-92 INIT. SMH

LENGTH SURFACE PLANNED RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2 @ 1672 CONDUCTOR ANHYDRITE T- B-1720 ELEVATION TD 5800 FORMATION

RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ 2520 Ft. W/ 100 SX Anhydrite Base @ 1720 Ft. W/ 80 40 SX Base Anyh. @ 600 Ft. W/ 50 SX 1/2 Plug @ Ft. W/ SX Surface @ Ft. W/ SX 2-3-93 @ 40 Plug 400 FT. W/ 10 SX MOUSE HOLE W/10 SX

WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SM DATE 1-27-92 TYPE OF CEMENT 60/40 6-70 STARTING TIME (AM/PM) DATE COMPLETION TIME 2: (AM/PM) DATE 1-28-92 CEMENT COMPANY Allied

STATE CORPORATION COMMISSION CONSERVATION DIVISION WICHITA, KANSAS