

TATE OF KANSAS  
 TATE CORPORATION COMMISSION  
 30 S. Market, Room 2070  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-02-J-117

API NUMBER 15-155-21,111-0000

LEASE NAME Melvin Minor Unit

WELL NUMBER 1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cases Div.  
 office within 30 days.

660 Ft. from N Section Line

3300 Ft. from W Section Line

SEC. 33 TWP. 25S RGE. 8W (E) or (W)

COUNTY Reno

LEASE OPERATOR Ramco Energy Corporation

ADDRESS P.O. Box 340 Great Bend, Kansas 67530

PHONE (316) 546-3300 OPERATORS LICENSE NO. 3536

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 8-24-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-29-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	368'	None
				5-1/2"	4032'	3006'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3770' and 5 sks. cement. Shot pipe @ 3006', pulled up to 1325', pumped 35 sks. cement, pulled up to 500', pumped 150 sks cement w/150 # balls and circulated to surface. 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ramco Energy Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of September, 2000

Irene Herzberg  
 Notary Public

My Commission Expires: \_\_\_\_\_

