

STATE OF KANSAS
 OIL AND GAS COMMISSION

WELL PLUGGING RECORD
 K.A.R.-82-3-117

D. S. Market, Room 2078
 Wichita, KS 67202

STATE OIL AND GAS COMMISSION
 10-16-97
 OCT 16 1997
 CONSERVATION DIVISION
 Wichita, Kansas

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

API NUMBER 15-155-21,115-8800

LEASE NAME Carolyn Miner

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E. Section Line

SEC. 33 TWP. 25S RGE. 8W (E) or (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 10-6-97

Plugging Completed 10-8-97

LEASE OPERATOR Ramco Energy Corporation

ADDRESS P.O. Box 340 Great Bend, Ks. 67530

PHONE (316) 786-1837 OPERATORS LICENSE NO. 3536

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

 (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3975'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	325'	None
				4-1/2"	3975'	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3740' and 4 sacks cement. Shot pipe @ 3200', 3000', pulled up to 1300', pumped 35 sacks cement, pulled to 750' and pumped 35 sacks, pulled to 375' and circulated 135 sacks cement. 60/40 Pos. 4% ael. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ramco Energy Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 97

Irene Herzberg
 Notary Public

My Commission Expires:

