

STATE OF KANSAS  
ATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
Olathe, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155 21,116-0000

LEASE NAME Charles Coleman

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E. Section Line

SEC. 33 TWP. 25 RGE. 8W (E) or (W)

COUNTY Reno

Date Well Completed         

Plugging Commenced 10-20-97

Plugging Completed 10-22-97

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS R.R. 1 Box 183B Great Bend, Kansas 67530

PHONE (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Gas

Oil, Gas, D&A, SWD, Input, Water Supply Well

Plugging proposal was approved on          (date)

Jack Luthi (KGC District Agent's Name).

ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.O. 4194'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	350'	None
				4-1/2"	4187'	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from          feet to          feet each sack. Plugged off bottom with sand to 3740' and 4 sacks cement. Shot @3200' and 3000'. Pulled up to 1400' and spotted 35 sks, cement and 150# hulls. Pulled to 400' and circulated 120 sks cement to surface, pulled rest of pipe and topped off with 5 sacks cement. 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524.

Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

Above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1997

*Irene Herzberg*  
Notary Public

My Commission Expires:         

