

STATE OF KANSAS
STATE CORPORATION COMMISSION
D. S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,117-0000

LEASE NAME Melvin Minor

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 25S RGE. 8W (E) or (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 9-24-98

Plugging Completed 9-25-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR Ramco Energy Corporation

ADDRESS P.O. Box 340 Great Bend, Ks. 67530

PHONE (316) 786-1837 OPERATORS LICENSE NO. 3536

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Luthi (KCC District Agent's Name)

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	347'	None
				5-1/2"	3969'	3010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3725' and 5 sacks cement. Shot pipe @3100' and 3010'. Pulled up to 1200', pumped 35 sks. cement, pulled to 700', pumped 35 sks. cement, pulled to 400', pumped 35 sks. cement, pulled to 200', pumped 90 sks. cement and circulated 60/40 pos 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts herein stated, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1998

[Signature]
Notary Public

My Commission Expires:

