

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-21,221-0000

LEASE NAME Shaffer

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 21 TWP. 25 RGE. 9W (E) or (W)

COUNTY Reno

Date Well Completed         

Plugging Commenced 12-1-92

Plugging Completed 12-3-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mach Petroleum, Inc.

ADDRESS P.O. Box 35583 Tulsa, Ok. 74153

PHONE#(918) 496-0442 OPERATORS LICENSE NO. 30146

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4012'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	192'	none
				5 1/2"	4012'	2853'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Sanded bottom to 3800', ran 5 sacks cement. Shot pipe @2853'. Mixed 35 sacks @1450', 35 sacks @800', circulated cement from 250' to surface, topped off. 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mach Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

DEC 11 1992  
12-11-92

R. Darrell Kelso (Employee of Operator) of          (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 10 day of December, 19 92

Irene Herzberg  
Notary Public

My Commission Expires:           
IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 1993