

LEASE NAME Moore

WELL NUMBER 1-13

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 13 TWP. 25 RGE. 9 (XXX(W))

COUNTY Reno

Date Well Completed

Plugging Commenced 9-1-95

Plugging Completed 9-6-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rama Operation Co., Inc.

ADDRESS P.O. Box 159 / Stafford, Ks. 67578

PHONE#(316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	217'	none
				5-1/2"	3982'	2539'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand at 3764' and 5 sacks cement. Shot pipe at 2701', and 2539'. Pulled up to 1300'. Pumped 35 sacks at 1300', pumped 35 sacks at 800', pulled to 270' circulated 100 sacks cement and topped off w/ 30 sacks cement. (60/40 4% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES:

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have known the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1995

Irene Herzberg
Notary Public

My Commission Expires:

USE ONLY ONE SIDE OF EACH FORM



RECEIVED
STATE CORPORATION COMMISSION
9-25-95
SEP 25 1995