

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,177-0000

LEASE NAME J.R.

WELL NUMBER 1

2310 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18 TWP. 25 RGE. 9 (E) or (W)

COUNTY Reno

Date Well Completed 09-16-91

Plugging Commenced 09-16-91

Plugging Completed 09-16-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 125 N. Market, Suite 1075 Wichita, KS 67202

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-16-91 (date)

by Mr. Sanders (KCC District Agent's Name).
to be filed

Is ACO-1 filed? by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 3/8</u>	<u>305</u>	<u>None</u>

9-23-91
SEP 23 1991

Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 1400' w/35 sacks cement thru drill pipe

Next Plug: @ 900' w/35 " " " " " 10 Sacks in Rat Hole

Next Plug: @ 350' w/35 " " " " " 10 Sacks in Mouse Hole

Top Plug: @ 60' w/25 " " " " " 5 sacks in water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gear Petroleum Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors

(Employee of Operator) or ~~Operator~~ XXXXXXXXXX of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 91

Paula Ann Laudick
Notary Public

My Commission Expires: _____



DRILLER'S WELL LOG

DATE COMMENCED: September 11, 1991
DATE COMPLETED: September 16, 1991

Gear Petroleum Co., Inc.
J. R. #1
N/2 NE SE
Sec. 18, T25S, R9W
Reno County, Ks.

0 - 70' Surface Soil, Sand
70 - 308' Red Bed, Shale
308 - 3200' Lime & Shale
3200 - 3917' Shale & Lime
3917 - 4000' Chert & Lime
4000' RTD

ELEVATION: 1717 K.B.

Surface Pipe: Set new
8-5/8", 23# pipe @ 305'
w/175 sacks 60/40 pozmix
2% gel 3% cc.

RECEIVED
STATE CORP. COMMISSION
9-23-91
SEP 23 1991

A F F I D A V I T

COM. # 1000
Wichita, Kansas

COUNTY OF BARTON
STATE OF KANSAS) ss.

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 20th day of September 1991.



Paula Ann Laudick
Notary Public