

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 20 TWP. 25S RGE. 9W E/W
Location as in quarters or footage from lines:

SW SW
 Lease Owner Murfin Drilling company
 Lease Name ~~XXXXXXXXXXXX~~ Conkling Well No. 1-20
 Office Address 617 Union Center Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 12-14-81
 Plugging completed 12-17-81
 Reason for abandonment of well or producing formation _____
Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ bottom T.D. 4182'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	310'	none
				4-1/2"	4097'	2578'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3850' and set 4 sacks cement. Shot casing @3365'. Squeezed hole with 15 sacks gel, 4 sacks hulls, 10 sacks gel, released plug and displaced with 100 sacks 50/50 pos, 2% gel. Plugging Completed.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1981
12-21-81
CONSERVATION DIVISION
Wichita Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 81



My Commission expires:

Irene Hoover
Notary Public.

WELL LOG

COMPANY Murfin Drilling Co.
 FARM Conkling NO. 1-20
 RID. NO. ---
 TOTAL DEPTH 4182'
 COMM. 3-5-81 COMP. 3-15-81
 CONTRACTOR Brandt Drilling Company

RECEIVED
 STATE CORPORATION COMMISSION
 255 R. 9W
 LOC. 790' FSL & 1260' FWL SW/4
 SEP 30 1981
 9-30-81
 CONSERVATION DIVISION
 COUNTY OF Wichita, Kansas
 KANSAS

CASING
 20 10
 15 5-8" set @ 810' w/250 sx 2% gel, 3% CC
 12 6
 13 4 1/2" set @ 4097' w/165 sx.

ELEVATION 1708' GL
 1713' KB
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Log Tops:


Stotler	2517 (-804)
Tarkio	2584 (-871)
Howard	2752 (-1039)
Topeka	2870 (-1157)
Heebner	3205 (-1492)
Toronto	3220 (-1507)
Douglas	3236 (-1523)
Brown Lime	3392 (-1679)
Lansing	3406 (-1693)
BKC	3766 (-2053)
RTD 4182'	

WELL FILE

State of Kansas
 County of Sedgwick } RR:

I, David L. Murfin, Drlg. Mgr. of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Conkling #1-20 well.



David L. Murfin
 David L. Murfin

Subscribed and sworn to before me this 17th day of March 19 81

My Commission Expires: Jan. 25, 1984

Ramona Gunn
 Ramona Gunn NOTARY PUBLIC