

Locate well correctly on above Section Plat

Haskell County, Sec. 34 Twp. 28S Rge. (E) 34 (W)
 Location as "NE/CNW/WSW" or footage from lines 660' FSL 660' FEL
 Lease Owner Amoco Production Company
 Lease Name K.H. Reimer Well No. 1
 Office Address P.O. Box 432 Liberal, Kansas 67901
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed December 13 19 61
 Application for plugging filed November 28 19 79
 Application for plugging approved December 4 19 79
 Plugging commenced January 3 19 80
 Plugging completed January 7 @ 4:00 P.M. 19 80
 Reason for abandonment of well or producing formation Glorietta Casing leak.

If a producing well is abandoned, date of last production September 19 74
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
 Producing formation Lansing "B" Depth to top 4185 Bottom 4187 Total Depth of Well 5630'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	lime	4045	4209	5 1/2"	5620'	1324.12'
				10 3/4"	763'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 1-4-80 Shot pipe @ 1421'.
- 1-5-80 Shot and started pipe @ 1321'. Pumped 35 sacks cement on stub displaced with mud.
- 1-7-80 Pulled pipe up to 813'. Pumped 60 sacks cement from 813' - 713' displaced with mud. Pulled pipe out of hole. Pumped 25 sacks cement from 53' to 3'. Cut surface pipe off below ground level and welded on steel plate.

Name of Plugging Contractor Reeves & Wilson, Inc. (If additional description is necessary, use BACK of this sheet) Permit #530
 Address P.O. Box 963 Woodward, Oklahoma 73801


STATE OF Kansas COUNTY OF Seward ss.
 Gale McCord (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gale McCord Gale McCord
 P. O. Box 432, Liberal, KS 67901
 (Address)

Subscribed and sworn to before me this 21st day of January, 1980

J. L. Dressen
 Notary Public.



RECEIVED
 STATE CORPORATION COMMISSION

JAN 24 1980

CONSERVATION DIVISION
 Wichita, Kansas