

15-187-60328-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA (SPUD 12/17/52)

LEASE NAME PLUMMER

WELL NUMBER 1-10

2540 Ft. from S Section Line

2540 Ft. from W Section Line

SEC. 10 TWP. 28S RGE. 40 (E) or (W)

COUNTY STANTON

Date Well Completed 1952

Plugging Commenced 09/26/97

Plugging Completed 09/28/97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09/12/97 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2194' Bottom 2401' T.D. 2401'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2194'	2401'	10-3/4"	300'	4'
				7"	2194'	930'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. MIRU PU. 11H W/1-1/2" TRG TO 2000'. PMP 90 BBLs MUD DWN 7" CSG. SPOT DWN TRG 40 SXS CMT & 3.5 SXS HULLS FROM 2194-1994'. TOH W/TRG. 1D HOLE W/MUD. PULL ON 7" CSG & SHOOT OFF @ 930'. CIRC HOLE W/MUD & PMP 50 SXS CMT PLG FROM 930-830'. PULL 7" CSG TO 400'. PMP 75 SXS CMT PLG FROM 400-250'. TOH W/7" CSG. 1D HOLE W/MUD TO 40'. PMP 15 SXS CMT PLG FROM 40-0'. CUT OFF & CAP 10-3/4" CSG 4' BELOW GL. INSCRIBE CAP. RDMO PU. RESTORE LOCATION. KCC WITNESS: STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God

(Signature) John A. Broman


JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

(Address) 3rd day of November, 1997.

Shirley J Childers  
Notary Public

My Commission Expires:



NOV 4 1997  
CONSERVATION DIVISION  
Wichita, Kansas