

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
8-27-01
AUG 27 2001
FORM CP-1 (3/79)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

CONSERVATION DIV.

API # 15-081-20963-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Exxon Mobil Corporation KCC LICENSE # 5208
(owner/company name) (operator's)

ADDRESS PO Box 4358 CITY Houston

STATE Texas ZIP CODE 77210 CONTACT PHONE # (713) 431-1828

LEASE Anshutz "A" WELL# 3 SEC. 2 T. 28 R. 33 (East, West)

NW - SW - NE SPOT LOCATION/OOOO COUNTY Haskell

1500 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2500 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 887' CEMENTED WITH 450 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 3013' CEMENTED WITH 425 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Please see attached

ELEVATION 2963'/2974' T.D. 3023' PBDT 2785' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Please see attached / According to KCC Rules &

Regulations & per directive of KCC District Representative

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Richard Lewis PHONE# () 316-544-5534

ADDRESS 200 W. 4th Street City/State Hugoton, KS 67951

PLUGGING CONTRACTOR Sargent & Horton KCC LICENSE # 31151

ADDRESS Rt. 1, Box 49BA, Tyrone, KS 73951 (company name) (contractor's)
PHONE # () 580-854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 12-7-01 plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/20/01 AUTHORIZED OPERATOR/AGENT: Colleen Peda
(signature)

AUG 27 2


CONSERVATION

PRELIMINARY B&A SKETCH-PLUGS WILL CHANGE PER THE DIRECTIONS OF THE KCC DISTRICT REPRESENTATIVE

COMPANY: Exxon Mobil Oil Corporation
WELL NAME: Anschutz "A"
WELL #: 3
API#: 15-081-20963
COUNTY: Haskell

| SURFACE CASING | | | |
|-------------------|---------|-------|--------|
| OD | WT / FT | GRADE | SET AT |
| 8 5/8" | 24 | | 887' |
| PRODUCTION CASING | | | |
| OD | WT / FT | GRADE | SET AT |
| 5 1/2" | 14 | | 3013' |
| TUBING | | | |
| OD | WT / FT | GRADE | SET AT |
| 2 3/8" | 4.7 | J-55 | 2700' |

| CAPACITIES (BBL/FT) | |
|---------------------|---------|
| 2 3/8" TBG | 0.00387 |
| 5 1/2" CSG | 0.0240 |
| 2 3/8" x 5 1/2" | 0.0186 |





KANSAS CONSERVATION COMMISSION

AUG 27 2001

CONSERVATION DIVISION

PROPOSED PLUGGING PROCEDURE FOR MOBIL OIL CORPORATION

WELL: ANSCHUTZ "A" # 3
FIELD: HUGOTON
COUNTY: HASKELL

THIS IS A CATEGORY III WORKOVER.

BOPE SPECIFICATIONS: CLASS V 300

NOTE: PERFORM ALL WELL WORK OPERATIONS IN ACCORDANCE WITH THE HPO WORKOVER OPERATIONS MANUAL.

NOTE: USE CLASS 'H', 16.4 PPG, 1.06 YIELD CEMENT FOR ALL PLUGS.

NOTE: PUMP 9.5 PPG MUD LADEN FLUID BETWEEN CEMENT PLUGS.

NOTE: NOTIFY KCC DISTRICT OFFICE IN DODGE CITY, KS PRIOR TO COMMENCEMENT OF WORK & WITHIN SUFFICIENT TIME TO WITNESS PLUGGING OPERATIONS.

NOTE: ENSURE PLUGGING FORMS HAVE APPROPRIATE INFORMATION NEEDED TO FILE APPROPRIATE PAPERWORK W/ THE KCC TO CONCLUDE PLUGGING OPERATIONS.

Check pressures on all casing strings daily and document on morning reports. Discuss safe blow down/well kill procedures with Exxon Mobil Workover Supervisor.

1. INSPECT JOBSITE FOR POTENTIAL HAZARDS & LOCATION CHARACTERISTICS THAT MAY IMPACT THE PLANNED WELLWORK AND/OR REQUIRE MODIFICATION OF THE PROCEDURE. INITIATE MOC PROCESS IF NEEDED.
2. SET & TEST RIG ANCHORS AS NEEDED.
3. **PLUG WELL AS DIRECTED BY KCC DISTRICT REPRESENTATIVE.** A GENERAL PLAN IS AS FOLLOWS, BUT SHOULD BE REVISED TO ENSURE ALL FORMATIONS (INCLUDING THE CHEYENNE FORMATION, DAKOTA FORMATION, ARBUCKLE FORMATION, ANY SALT FORMATIONS & ANY FRESH & USABLE WATER ZONES) ARE ISOLATED AS PER THE SPECIFICATIONS OF THE KCC.
4. MIRU. LOAD WELL W/ FSW.
5. REMOVE TREE. INSTALL BOP'S & TEST.
6. RU WL UNIT W/ CLASS II LUBRICATOR & TEST. MAKE GAUGE RING & JUNK BASKET RUN TO 2690'. POH.
7. RIH & SET 5 1/2" CIBP @ 2680'. POH.
8. RIH & DUMP BAIL 3 SX CEMENT ON TOP OF CIBP FROM 2660' - 2680'. POH. RD WL UNIT.
9. RIH W/ WORKSTRING TO 2600'.
10. WOC. TEST 5 1/2" CSG TO 500 PSI.
11. CIRCULATE 9.5 PPG MUD.
12. POH W/ WORKSTRING TO 937'.

13. SET 125 SX CEMENT PLUG FROM 3' - 937'.
14. POH W/ WORKSTRING.
15. REMOVE BOP'S.
16. CUT & CAP WELL 3' BELOW GROUND LEVEL.
17. RD/MO.

8/15/01



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

EXXONMOBIL Oil Corp
PO Box 4358
Houston, TX 77210-4358

August 28, 2001

Re: ANSCHUTZ A UT #3
API 15-081-20963-00-00
NWSWNE 2-28S-33W, 1500 FNL 2500 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888

Sincerely,
A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

EXXONMOBIL Oil Corp
PO Box 4358
Houston, TX 77210-4358

November 30, 2001

Re: ANSCHUTZ A UT #3
API 15-081-20963-00-00
NWSWNE 2-28S-33W, 1500 FNL 2500 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888

Sincerely,

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor