


WELL PLUGGING RECORD

15-187-00018-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

21 Stanton County, Sec. 10 Twp. 28 Rge. (E) 41 (W)
Location as "NE/CNW/SW" or footage from lines C SW
Lease Owner Musgrove Drilling Company
Lease Name CRAIG Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 22, 1961 19
Application for plugging filed verbally July 22, 1961 19
Application for plugging approved verbally July 22, 1961 19
Plugging commenced July 22, 1961 19
Plugging completed July 23, 1961 19
Reason for abandonment of well or producing formation D& A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5565' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1505'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/heavy mud to 1450'
Set 1st plug at 1450' w/25 sx cement
Set 2nd plug at 500' w/25 sx cement & 1/4 sx hulls
Set 3rd plug at 40' w/ 20 sx cement & 1/4 sx hulls

RECEIVED
STATE CORPORATION COMMISSION

8-1-61 AUG 1 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wardco Drilling Co. Inc.
Address West 10th Street, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Emil E. Bowers (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
801 Union Center, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 61

My commission expires June 16, 1963

Reah Joyce Hepler
Notary Public.

CONTRACTOR'S WELL LOG

15-187-00018-00000

COMPANY:	Musgrove Drilling Company
CONTRACTOR:	Wardco Drilling Co., Inc.
FARM:	CRAIG #1
LOCATION:	C SW Sec. 10-28-41W Stanton County, Kansas
COMMENCED:	June 28, 1961
COMPLETED:	July 22, 1961

0	100	Surface Clay - sand
100	325	Sand
325	350	Sand & Gyp
350	700	Sand & Shale & Gyp
700	1050	Red Bed
1050	1200	Red Bed & Streaks Sand
1200	1265	Gyp & Streaks Shale
1265	1313	Sand & Anhydrite Streaks
1313	1450	Shale
1450	1681	Sand - Streaks Shale
1681	1715	Anhydrite
1715	2026	Shale & Shells
2026	3315	Lime & Shale
3315	3898	Lime, Shale & Chalk
3898	4250	Lime & shale
4250	4360	Chalky Lime
4360	5000	Lime
5000	5095	Lime & Shale
5095	5295	Shale
5295	5335	Lime & Shale
5335	5361	Shale & Sand
5361	5565	Lime
	5565	Total Depth

Set 8-5/8" surface at 1505' w/745 scks cement
 DRY & ABANDONED

ELECTRIC LOG TOPS:		ELEVATIONS:	3368' K. B.
Elmont	3216' (+ 152)		3365' D. F.
Topeka	3363' (+ 5)		
Heebner	3648' (- 280)		
Toronto	3673' (- 305)		
Lansing	3704' (- 336)		
Base Kansas City	4294' (- 926)		
Marmaton	4334' (- 966)		
Cherokee	4524' (-1158)		
Morrow	5066' (-1698)		
Keyes	5296' (-1928)		
Miss. (Chester)	5368' (-2000)		
Ste. Genevieve	5396' (-2028)		
St. Louis	5462' (-2094)		


RECEIVED
 STATE CORPORATION COMMISSION
 AUG 1 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the CRAIG #1, C SW, Section 10-28-41W, Stanton County, Kansas, as reflected by the files of Wardco Drilling Co., Inc.


 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 31st day of July, 1961.


 Leah Faye Hefke, Notary Public

My Commission expires June 16, 1963.