

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 081-12200
LEASE NAME Fletcher
WELL NUMBER 21-C

30002-0000

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

3300 FSL Ft. from S Section Line
1980 FEL Ft. from E Section Line
SEC. 8 TWP. 28S RGE. 34 (X) or (W)
COUNTY Haskell
Date Well Completed 11/28/64
Plugging Commenced 7/22/95
Plugging Completed 10/02/95

LEASE OPERATOR OXY USA Inc.
ADDRESS P. O. Box 26100
PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by Richard Lacey (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Morrow Depth to Top 5240 Bottom 5362 T.D. 5500 ✓

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|------|--------|--------|------------|
| Morrow | OIL | 5240 | 5362 | 8 5/8" | 1926 ✓ | |
| | | | | 5 1/2" | 5461 ✓ | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Displaced hole w/ 9# mud. Set CIBP @ 5190'. Spot 1 sks cement on plug. Pumped 47sks cmt down 8 5/8 & 5 1/2 csg annulus. Cmt broached thru 8 5/8 csg & circ to surface outside of surface pipe. Displaced annulus. Contacted KCC rep Steve Durrant for revised plugging orders. TIH w/97 lbs 2 7/8 tbg & spotted 30sks cmt plug @ 3010'. (See back of form)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson License No. 5866

Address Box 466, Ulysses, KS 67880


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100



SUBSCRIBED AND SWORN TO before me this 30th day of November, 1995

[Signature]
Notary Public

7-14-99
My Commission Expires: _____

RECEIVED
STATE CORPORATION COMMISSION
12-4-95 DEC

TOOH & ld 35jts tbg & spotted 30sks plug @ 1980'. TOOH & ld 34jts to 850'. Attempted to fill 5 1/2 csg to surface. Pmp'd 86sks & lost circ to surface. Displaced tbg & TOOH. TIH w/ tbg & tagged TOC @ 625'. Contacted KCC rep Steve Phiefer for additional plugging orders. RIH w/ large perf gun. Perf'd @ 610-611 w/4 SPF. Estb circ dn csg to surface. Pmp'd 140sks cmt w/cmt returns to surface. Let set 1 hr & filled csg to surface. Cut off csg 5' BGL & capped. Reclaimed location.

