


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Haskell County. Sec. 23 Twp. 28S Rge. (E) 34 (W)
Location as "NE/CNW/SW" or footage from lines C SW/4 SW/4
Lease Owner Graham-Michaelis Drilling, Inc.
Lease Name Eubank "A" Well No. 2-23
Office Address 211 North Broadway, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed May 28, 1960
Application for plugging filed Sept. 17, 1969
Application for plugging approved Sept. 17, 1969
Plugging commenced Sept. 20, 1969
Plugging completed Sept. 23, 1969
Reason for abandonment of well or producing formation Non Commercial



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production August 1969
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves - Box E, Sublette, Kansas
Producing formation Lansing Depth to top 4120 Bottom 4180 Total Depth of Well 5550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	Oil & Water	4175	4180	8 5/8"	857'	none
				4 1/2"	4258'	1935'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rig up pump truck and mix 15 sacks cement and 1 sack hulls to plug off perms. Stop plug at 4,000'. Mix 5 sacks gell at 1,000'. Pump 40 sacks cement at 800' to 700'. Fill hole with mud to 50'. Put 15 sacks cement at 45' to 0'

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1969
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
Address P. O. Box 506, Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John L. James (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John L. James
211 North Broadway, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1969
My commission expires July 25, 1972
Muriel F. C. Jeram
Muriel F. C. Jeram Notary Public.



WELL RECORD:

LOCATION:

SW SW Sec. 23-28-34
Haskell County, Kansas

Commenced: 5/3/60
Completed: 5/21/60
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling Co.
Liberal Division
Box 896
Liberal, Kansas

CASING RECORD:

28 Jts. 8 5/8" 8rd Thd 24# Casing
cemented w/450 sx 2% gel 2% cc

	LOG	
Sub-Soil, Clay, Sand & Gravel	0 -	310
Sand & Shale	310 -	415
Shale	415 -	660
Red Bed & Shells	660 -	858
Red Bed	858 -	1193
Shale, Shells & Red Bed	1193 -	1413
Shale & Red Bed	1413 -	1934
Shale	1934 -	2090
Shale & Shells	2090 -	2530
Shale & Anhy	2530 -	2647
Shale & Lime	2647 -	4289
Lime	4289 -	4395
Lime & Shale	4395 -	5137
Lime	5137 -	5213
Lime & Shale	5213 -	5394
Lime, Shale & Sand	5394 -	5464
Lime	5464 -	5550

5550' - Total Rotary Depth

The undersigned, Graham-Michaelis Drilling Company, Liberal Division, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well as taken from the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING CO.
LIBERAL DIVISION

By 
H. R. Michaelis

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1969
CONSERVATION DIVISION
Wichita, Kansas