

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-081-10003-00-01
API NUMBER 1508110003

LEASE NAME GREGG, EM

WELL NUMBER 4

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 32 TWP. 28S RGE 34 (E) or (W)

COUNTY HASKELL

Date Well Completed 10-15-1960

Plugging Commenced 12-28-2002

Plugging Completed 1-1-2003

RECEIVED
1-10-03
JAN 10 2003
KCC WICHITA

NOTICE: TYPE OR PRINT
Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-23-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation LANSING MARMATON, KANSAS CITY, Depth to Top 4061 Bottom 4670 T.D. 5502

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
LANSING	GAS	4061	4071	8-5/8	1853	0
KANSAS CITY	GAS	4110	4567	5-1/2	5501	900
MARMATON	GAS	4664	4670			

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. SET CIBP AT 4000. PULL FREE POINT AND SHOOT OFF 5-1/2 CSG AT 900. PUMP 80 SXS CMT AT 700. PUMP 110 SXS CMT AT 300. PUMP 10 SXS CMT AT 40. CUT OFF AND CAP 8-5/8 CSG 4 BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor EAGLE WELL SERVICE License No. 7407

Address 1661 W. 7TH LIBERAL, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 7 day of January, 20 03

Lori Pearson

My Commission Expires: 2/26/05

Notary Public
LORI PEARSON
Notary Public, State of Texas
My Commission Expires
February 26, 2005
Form CP-4
Revised 05-88

OR