

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-081-75003 ²⁰¹⁷⁰⁻⁰⁰⁰⁰

LEASE NAME K. H. Reimer /B/

WELL NUMBER 1

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 34 TWP. 28S RGE. 34 (X) or (W)

COUNTY Haskell

Date Well Completed 02-64

Plugging Commenced 6-10-87

Plugging Completed 6-15-87

LEASE OPERATOR Amoco Production Company

ADDRESS P. O. Box 432 Liberal, KS 67901

PHONE#(316) 624-6241 OPERATORS LICENSE NO. 5952

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation St. Genevieve Depth to Top 5438 Bottom 5442 T.D. 5600

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	5293	98	8-5/8	747	Surface 0'
St. Genevieve	Oil	5438	42	7	5619	Production 1440'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Welex set CIBP @5200' x capped w/25 sx cmt; pump 50 sx cmt 1440' to 1340' x laydown 5-1/2" to 800' x pump 50 sx cmt 800 to 700. Put bridge x 10 sxs cmt 40' to 4 x cut off 8-5/8, 4' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing License No. 6497

Address Box F. Sublette, KS


STATE OF Kansas COUNTY OF Haskell, ss.

Larry L. Smith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry L. Smith

(Address) P. O. Box 432 Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 87



Appointment Expires: 4-28-89

RECEIVED
STATE CORPORATION COMMISSION

Notary Public

JUN 30 1987

6-30-87

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84