


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

HASKELL

County. Sec. 30 Twp. 28S Rge. 31W (W)

Location as "NE/CNW/SW" or footage from lines C SW/4
Lease Owner Graham-Michaelis Drilling Co.
Lease Name EMMONS Well No. 1
Office Address 211 North Broadway, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 8-14-55 19__
Application for plugging filed 6-4-57 19__
Application for plugging approved 11-27-57 19__
Plugging commenced 11-27-57 19__
Plugging completed 11-30-57 19__
Reason for abandonment of well or producing formation Low Production

If a producing well is abandoned, date of last production March 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rivas, Box 8, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2772 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand, Gravel, Clay, & Blue shale</u>		<u>0</u>	<u>555*</u>	<u>8 5/8"</u>	<u>555*</u>	<u>0</u>
<u>Red Bed, Amhy. & Shale</u>		<u>0</u>	<u>2772*</u>	<u>5 1/2"</u>	<u>2772*</u>	<u>1213*</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/crushed rock to 2700*. Dumped 5 sax cement @2700*.
Dumped 5 sax cement @2700* w/dump bailer. Top of cement, 2665*.
Filled hole w/mud to 550*, set rock bridge dumped 20 sax cement.
Top of cement, 490*. Filled hole w/mud to 35*, set rock bridge,
dumped 10 sax cement for cap.

RECEIVED
STATE CORP. COM. COMMISSION
12-13-57
DEC 13 1957

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address P. O. Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
O. W. Woodland (employee of owner) ~~or authorized operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaelis Drilling Co.

(Signature) *O. W. Woodland*
211 No. Broadway, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1957

My commission expires 1/7/61.

PLUGGING
FILE SEC 30T 28 R 31A
BOOK PAGE 17 LINE 38

Notary Public.

15-081-00196-0000

~~RECORDED~~

Location: Sec. 30-285-314
Banks County, Kansas

Commenced: August 8, 1950

Completed: August 14, 1950

Operator: Michaelis Drilling Company
1010 East Second Street
Wichita 7, Kansas

Contractor: Michaelis Drilling Company
1010 East Second Street
Wichita 7, Kansas

Casing Record: 8 - 8/8" - 855' w/300 sacks cement
8 - 1/2" - 2,771' w/300 sacks cement

Log

Sand & Gravel	107
Sand	260
Gravel & Sand	465
Clay & Blue Shale	585
Sand	814
Blue Shale	743
Red Bed	870
Blue Shale & Sand	910
Red Bed & Sand	1180
Argillite	1200
Red Bed & Shale	1975
Red Bed & Shale /with some gyp	2100
Arg. Shale & Shale	2778. FT.

Top of Livingston	3080'
Top of upper Arader	2712'
Top of lower Arader	2742'

STATE OF KANSAS)
) ss.
COUNTY OF SEDWICK)

The undersigned, Michaelis Drilling Company, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

MICHAELIS DRILLING COMPANY

[Signature]
John L. Jansen, Leslie Lee



came to before me
September, 1950.

[Signature]
Notary Public.
Expires: 11/7/57

PLUGGING
FILE SEC 30T 28 R31W
BOOK PAGE 17 LINE 38