

15-081-00176-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Haskell County, Sec. 6 Twp. 28 Rge. 32 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C/NW/4

Lease Owner Walter Kuhn

Lease Name Hawes Well No. 1

Office Address 726 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12 - 19 58

Application for plugging filed 4-9- 19 62

Application for plugging approved 4-11- 19 62

Plugging commenced 4-18- 19 62

Plugging completed 4-18- 19 62

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Victor Simoncic

Producing formation Hugoton Depth to top 2720 Bottom 2794 Total Depth of Well 2794 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Casing	- - -	0	2720	7" OD	2720	None
Casing	- - -	0	580	10" 3/4 OD		None
Herington Krider	Void	2720	2794			
Winfield						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Cement plug from 2693' to 2794' by Sun Cementing Company, Max. press 1000#. Used 35 sacks cement. Water from 43' to 2693'. Set cement plug from 0 to 43' by Sun Cementing Company, Used 15 sacks cement. 7" casing was set @ 2720' and cement was circulated to surface. Cut 7" and 10 3/4" casing off 3' below ground level.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1962 4-25-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Walter Kuhn  
Address 726 Union Center  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Walter Kuhn (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Kuhn  
726 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of April, 19 62

My commission expires May 16, 1963  
Lucille Kerr  
Notary Public.

LEASE: Hawes #1  
CONTRACTOR: Earl F. Wakefield  
OPERATOR: Walter Kuhn  
COMM: 12/7/58 CORP; 12/12/58

LOCATION: C NW/4  
SECTION 6-28S-32W  
Haskell County, Kansas  
CASING: 10 3/4" Set at 580 feet  
7" Set at 2720 KB

Elevation: 2937 G.L.  
2949 K.B.

Sandy Clay	60
Sand	250
Gravel Sand	350
Blue Gumbo	450
Gravel	485
Blue Shale	588
Blue and Red Shale	985
Red Bed	1360
Red Bed, Gyp	1410
Red Bed, Gyp salt	1760
Anhydrite	1815
Shale Red Bed	1963
Lime	1973
Red Bed and Shale	2170
Red Bed, Shale, Anhydrite	2303
Shale, Lime	2441
Lime	2590
Lime and Shale	2675
Lime and Red Shale	2722
T. D.	2722

RECEIVED  
STATE CORPORATION COMMISSION

MAY 10 1962

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the Hawes #1 well, located Center Northwest Quarter (C NW/4) of Section 6, Township 28 South, Range 32 West, Haskell County, Kansas.

EARL F. WAKEFIELD

By F. S. Bacher

Subscribed and sworn before me this 22nd day of December, 1958.

C. A. Snow  
C. A. Snow Notary Public

My commission expires July 26, 1962