


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Haskell County, Sec. 13 Twp 28S Rge. 32 (25) (W)  
Location as "NE/CNW%SW%" or footage from lines C/ SW/4  
Lease Owner Graham-Michaelis Drilling Co.  
Lease Name Gilstrap Well No. 1  
Office Address 211 North Broadway, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed May 16 19 55  
Application for plugging filed February 1 19 59  
Application for plugging approved February 5 19 59  
Plugging commenced February 26 19 59  
Plugging completed February 28 19 59  
Reason for abandonment of well or producing formation Low production

If a producing well is abandoned, date of last production December 19 58  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merl Rives, Garden City, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2,748 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, Gravel, Sandy Shale, Silt and Blue Shale		0'	582'	8-5/8"	582'	0'
Shale, Sand, Red Bed, Gyp & Anhydrite		582'	2,748'	5 1/2"	2,747'	1,334'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 350' set 10' rock bridge. Mixed and run 20 sacks cement with dump bailer. Mud to 40', 10' rock bridge with 10 sacks cement to base of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 12 1959  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Company  
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
O. W. Woodland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. W. Woodland - O. W. Woodland  
211 North Broadway, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 59

My commission expires 1-7-61

V. D. Grier

Notary Public.

**PLUGGING**  
FILE SEC 13 T. 28 R. 32W  
BOOK PAGE 14 LINE 17

