

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-26565-00-00  
Spot: SWSWNE5W Sec/Twnshp/Rge: 25-30S-16E  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: DENNIS SELLER Well #: 1-25  
County: WILSON Total Vertical Depth: 1105 feet

Operator License No.: 34769  
Op Name: CHEROKEENRG LLC  
Address: P.O. BOX 111 112 SOUTH 5TH STREET  
NEODESHA, KS 66757

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1095		
PROD	4.5	1095		135 SX
SURF	8.625	23		4 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/12/2015 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: PAM GRAVES Company: CHEROKEE NRG, LLC Phone: (620) 432-1840

Proposed Plugging Method: Run 1" to bottom, gel hole, spot 50' cement plug, pull up to 500', spot 50' cement plug, pull up to 225', cement to surface, pull tubing out and top off cement. Cut wellhead off below ground level and restore location.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 01/12/2015 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was lowered to TD and 70 sacks of cement pumped. The cement string was pulled to 500 ft and 27 sacks pumped. The cement string was pulled to 150 ft and 7 sacks pumped. The cement string was removed and the well topped off with 7 sacks. A total of 111 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
843	846		
732	734		
671	676		

RECEIVED  
KCC DIST #3  
AUG 05 2015  
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

8/19/15 ckm

District: 03

Signed Alan Dunning  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

AUG 10 2015

CONSERVATION DIVISION  
WICHITA, KS