

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-21114-00-00  
Spot: SW Sec/Twnshp/Rge: 16-24S-31W  
2310 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: BIERNACKI Well #: 2-16  
County: FINNEY Total Vertical Depth: 2725 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2723	0	WITH 500 SX CMT
SURF	8.625	390		WITH 230 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2015 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

KCC WICHITA  
AUG 05 2015  
RECEIVED

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/22/2015 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:


FILL 4 1/2" CASING WITH CMT FROM 2682' TO 0' USING 250# HULLS & 185 SX CMT.  
PRESSURE TO 500#. HOLDING. PUMP 35 SX CMT DOWN THE ANNULUS &  
PRESSURE TO 300 PSI. HOLDING.

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

8/19/15 CKM

RECEIVED  
JUL 31 2015  
KCC DODGE CITY