

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-10481-00-00
Spot: SESESW Sec/Twnshp/Rge: 3-24S-15W
334 feet from S Section Line, 2970 feet from E Section Line
Lease Name: NAGEL B Well #: 1
County: STAFFORD Total Vertical Depth: 4124 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3660		WITH 2 SX CMT
CIBP		3920		WITH 2 SX CMT
PROD 5.5		4124	0	WITH 150 SX CMT
SURF 8.6625		252		WITH 185 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/28/2015 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 682-9100

Proposed Plugging Method: SET CIBP @ 3920' & 2 SX CMT. SET CIBP @ 3660' & 2 SX CMT. RUN BOND LOG. PERFORATE & RUN TBG TO 1000'. FILL UP BOTH SIDES WITH CMT. PULL TBG & TOP OFF.

KCC WICHITA
AUG 05 2015
RECEIVED

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2015 10:48 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 3920' WITH 2 SX CMT. SET CIBP @ 3660' WITH 2 SX CMT. RAN BOND LOG. TOC @ 350'. PERFORATE AT 312'. RUN 2 3/8" TBG TO 1000'. CIRCULATED CMT THROUGH 8 5/8" ANNULUS & 5 1/2" ANNULUS TO SURFACE. CIRCULATED CMT IN 5 1/2" X 8 5/8" ANNULUS & 2 3/8" X 5 1/2" ANNULUS. USED A TOTAL OF 140 SX CMT. LAY DOWN TBG & TOPPED OFF 5 1/2" CASING WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3984	4020		MISSISSIPPI
3710	3820		LANSING/KANSAS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

8/19/15 CKM

District: 01

Signed Robert Dickerson
SA (TECHNICIAN)

RECEIVED
JUL 29 2015
KCC DODGE CITY