

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20477-00-00
Spot: NESWNW Sec/Twnshp/Rge: 32-15S-10W
3627 feet from S Section Line, 4355 feet from E Section Line
Lease Name: ZVDLANEK A Well #: 4
County: ELLSWORTH Total Vertical Depth: 3327 feet

Operator License No.: 3682
Op Name: CONNELL, MARK ALLEN
Address: 606 W ALBRO ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		627		
PROD	5.5	3326		200 SXS CMT
PROD	5.5	3327		200 SX
SURF	8.625	230		150 SXS CMT
SURF	8.625	235		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/30/2015 12:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: MARK CONNELL Company: MARK CONNELL Phone: (620) 786-1228

Proposed Plugging Method: AS PER KCC RULES & REGS. OPERATOR WAS SENT A TA - N.O.V. LETTER ON THIS WELL.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/30/2015 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1300' AND 1000'. RUN TUBING TO 3250' AND PUMP 25 SX'S CEMENT. PULL TUBING TO 1350' AND PUMP 40 SX'S WITH 2% CC. PULL TUBING UP TO 800' AND LET SET AWHILE. TAGGED CEMENT AT 825'. PUMPED 25 SX'S AT 800', PULLED TUBING TO 280' AND CIRCUALTED CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3282	3288	CSG	

Remarks: WELL WAS TWO STAGED FROM 627' TO SURFACE ON 10-19-77. QUAILTY WELL TICKET #1438. LOG TECH OF KS #8528.

Plugged through: TBG

District: 02

Received
KANSAS CORPORATION COMMISSION
AUG 12 2015
CONSERVATION DIVISION
WICHITA, KS

Signed

Virgil Clothier

(TECHNICIAN)

8/19/15 ccm

✓