

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21582-00-00
Spot: NWNE Sec/Twnshp/Rge: 24-32S-21W
4621 feet from S Section Line, 1447 feet from E Section Line
Lease Name: LOESCH Well #: 2
County: CLARK Total Vertical Depth: 6438 feet

Operator License No.: 31691
Op Name: CORAL COAST PETROLEUM, L.C.
Address: 8100 E 22ND ST N BLDG 600, STE R
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5150		WITH 2 SX CMT
CIBP		5420		
CIBP		6324		
PROD	5.5	6438	4360	WITH 175 SX CMT
SURF	8.625	627		WITH 400 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/03/2015 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5150' WITH 2 SX CMT. PLUG AT 1070' WITH 15 SX GEL & 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 60' TO SURFACE WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2015 11:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5150' WITH 2 SX CMT. 1ST PLUG AT 1081' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 655' WITH 50 SX CMT. 3RD PLUG AT 262' WITH 40 SX CMT. 4TH PLUG AT 65' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6328	6335		
6308	6318		
5193	5228		

KCC WICHITA
AUG 10 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

8/19/15 ckm

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
AUG - 7 2015
KCC DODGE CITY