

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-25717-00-00
Spot: S2NENENW Sec/Twnshp/Rge: 34-30S-17E
536 feet from N Section Line, 2196 feet from W Section Line
Lease Name: CLAMPITT MARVIN Well #: 34-1A
County: WILSON Total Vertical Depth: 1126 feet

Operator License No.: 34420
Op Name: EXODUS GAS & OIL LLC
Address: 1001 MCKINNEY ST., STE. 804
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1124		133 SX
SURF	8.625	23		6 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 03/31/2015 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: RAY GILBERT Company: EXODUS GAS & OIL Phone: (620) 820-9687

Proposed Plugging Method: Cement to surface. Cut off casing 3ft below ground level

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 03/31/2015 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 2.375 inch cement string was lowered to 1118 ft and 70 sacks of cement pumped. The cement string was pulled to 550 ft and 28 sacks of cement pumped. The cement string was pulled to 250 ft and 21 sacks of cement pumped. The cement string was removed and the well topped off with 3 sacks of cement. A total of 122 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST # 3
AUG 05 2015
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

8/19/15 ckm

District: 03

Signed Alan M. Dunning
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

AUG 10 2015

CONSERVATION DIVISION
WICHITA, KS