

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21371-00-00  
Spot: W2SENE Sec/Twnshp/Rge: 20-29S-17W  
1980 feet from N Section Line, 815 feet from E Section Line  
Lease Name: HAMMOND Well #: 1-20  
County: KIOWA Total Vertical Depth: 4885 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4797		WITH 2 SX CMT
PC		3638		WITH 200 SX CMT TOC 2740'
PROD 5.5		4882	1800	WITH 100 SX CMT
SURF 8.625		438		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/06/2015 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4790' WITH 2 SX CMT. PUMP 150# HULLS & 25 SX CMT AT 3440'. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 490' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/06/2015 1:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4797' WITH 2 SX CMT. PUMP 25 SX CMT WITH 150# HULLS .  
PRESSURED TO 1500#. TOC 3300'. 1ST PLUG AT 1111' WITH 15 SX GEL & 50 SX  
CMT. 2ND PLUG AT 516' WITH 50 SX CMT. 3RD PLUG AT 39' WITH 30 SX CMT.  
CMT CIRCULATED.

KCC WICHITA  
AUG 10 2015  
RECEIVED

Perfs:

Top	Bot	Thru	Comments
4842	4854		
3487	3492		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

8/19/15

District: 01

Signed: [Signature]  
(TECHNICIAN)

RECEIVED  
AUG - 7 2015  
KCC DODGE CITY