

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-28352-00-00
Spot: SEWNENESE Sec/Twnshp/Rge: 28-29S-15E
2280 feet from S Section Line, 920 feet from E Section Line
Lease Name: LANDER Well #: 7
County: WILSON Total Vertical Depth: 1229 feet

Operator License No.: 34471
Op Name: LEGEND OIL & GAS LTD.
Address: 555 NORTHPOINT CNTR EAST SUITE
ALPHARETTA, GA 30022

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	42		8 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/24/2015 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TERRY CARROLL Company: LEGEND OIL & GAS LTD Phone: (800) 917-1618

Proposed Plugging Method: Load hole with jell, spot 5 sacks of cement at TD 1,229ft, 5 sacks of cement at top of Oswego, then cement 350ft to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 06/24/2015 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1226 ft and 5 sacks of cement pumped. The cement string was pulled to 860 ft and 5 sacks of cement pumped. The cement string was pulled to 350 ft and 38 sacks of cement pumped. The cement string was removed and the well topped off with 12 sacks of cement. Gel spacers were used between plugs. A total of 60 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DIST # 3
AUG 05 2015
CHANUTE, KS

AD

Remarks:

Plugged through: OH

8/19/15 ckm

District: 03

Signed Alan Dunning
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

AUG 10 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3